

# LOSS DRAFT INSPECTION CARD

(Laminated and Pocket-Sized)

## ■■ #1 RULE: MATERIALS ≠ INSTALLED WORK ■■

Insurance pays for INSTALLED materials, not delivered materials!

### COMPLETION PERCENTAGE GUIDELINES

| %       | What This Means                        | What to Photo                                               | What to Note                                  |
|---------|----------------------------------------|-------------------------------------------------------------|-----------------------------------------------|
| 0-25%   | Demolition done, framing started       | Debris removed, framing in progress, materials on site      | "Demolition complete. Framing 25% complete."  |
| 25-50%  | Framing done, rough-ins in progress    | Framing complete, electrical/plumbing rough-ins, insulation | "Framing complete. Rough-ins 50% complete."   |
| 50-75%  | Drywall going up, finish work starting | Drywall installed, taping/mudding, primer applied           | "Drywall installed. Taping 75% complete."     |
| 75-100% | Paint, flooring, trim installed        | Finished surfaces (painted walls, flooring down, trim)      | "Repairs complete. Paint/flooring/trim done." |
| 100%    | Job done, ready for occupancy          | Entire area finished, no deficiencies                       | "Repairs 100% complete per scope."            |

### PHOTO REQUIREMENTS (Two-Photo Rule)

For Each Repair Area:

- **Context shot** - Wide angle showing entire area
- **Detail shot** - Close-up of completed work
- **Comparison angle** - Same angle as "before" photo if available
- **Evidence of installation** - Not just materials, but work DONE

**Example: Roof Replacement**

- ✓ Wide shot of entire roof (shows full coverage)
- ✓ Close-up of shingle pattern (shows quality)
- ✓ Ridge cap detail (shows proper finishing)
- ✓ Flashing at chimney (shows waterproofing)

**Example: Interior Water Damage**

- ✓ Wide shot of repaired room (shows entire restoration)
- ✓ Ceiling repair (drywall installed, textured, painted)
- ✓ Wall repair (same)
- ✓ Flooring replacement (installed, not stacked)

### COMMON PITFALLS (Avoid These!)

- **Materials on site = work complete** - NO! Shingles in driveway ≠ roof installed.
- **Not comparing to scope** - Verify work matches approved scope. Note deviations.
- **Over-reporting completion %** - Don't inflate to speed fund release. Be accurate.
- **No context photos** - Wide shot shows scope; detail shot shows quality. Need both.
- **Missing "before" comparison** - Reference initial loss photos to show progress.